

VES Fields Clearing and Grading Permit Project

Scope of Work: Storm drainage system; concrete sidewalk and curb.

To include all incidental work to complete this scope. All work to be in accordance with King County specifications and ESM Engineering plans (ESM Engineering, 181 South 333rd Street, Building C, Suite 210, Federal Way, WA. 98003).

Sheets 1 through 11

Plan dates Sheet 1 6.3.11 hand written
Sheet 2 6.1.2011
Sheet 3 6.1.2011
Sheet 4 5.31.2012
Sheet 5 6.1.2011
Sheet 6 6.1.2011
Sheet 7 5.31.12
Sheet 8 6.1.2011
Sheet 9 6.1.2011
Sheet 10 6.1.2011
Sheet 11 6.1.2011

Division 2

Storm Drainage: Sheet UT-01 4 of 11

1. Install and supply area drain# 4.
2. Install and supply starting at C.B.#4 install 12" SD to C.B.# 5, C.B. #6, C.B #7 and C.B. #8. CB's are to be installed at the center line of the road.

Asphalt paving: Sheet DT-02 6 of 11 and sheet ST-01 page 3 of 11. See detail on sheet. Assume 2" of Class B Asphalt and 6" of ¾- crushed rock as the sub-base.

3. Paving is to be in two separate parts. One will be preparation of the west parking lot site to include the entrance from the Vashon Highway and the Harbor School parking lot.
4. Paving 2 is the North parking lot to include the entrance road and fire truck turn around.
5. Complete striping of the parking areas as well as barrier free ADA markings.

Excavation, grading and compaction:

6. Excavation and compaction for asphalt work.
7. Excavation and compaction for sidewalk work.
8. Excavation and compaction for ADA slabs.
9. Move 5 boulders from West parking entrance to South West entrance on the North side running East- West.

Grading:

10. Grading for parking lot.
11. Grade bank at front of water storage tanks to a 3:1 slope.
12. Grade sidewalk.

Division 3

Concrete: ST-01 and DT-02 details. Note: wire fabric to 6x6 10g.

13. Concrete curb per DT-02 approximately 984 LF.
14. Concrete sidewalk 5' per detail DT-02 approximately 325 LF.
15. Concrete sidewalk 15' per detail DT-02 approximately 45 LF.
16. ADA parking areas two sets approximately 45 LF by 20 LF.
17. Demolition of two existing ADA Stalls in the West and North parking areas.
18. Bollard slab.

Questions on the scope or requests for copies of the plans should be sent to:

F. Mitch Treese
P.O. Box 1947
Vashon Island, WA. 98070
Cell Phone 206-200-5663
fmitchtreese@gmail.com