

Point Robinson Lighthouse Modifications

Interior Modifications

- Add 2 vertical handholds at 28 inches along the top right upper stairwell.
Presently, the railing comes up the stairwell then stops, and it is just a flat wall for the remaining four-to-five feet.
- Add a 2 inch bronze post to 40 inch center of the curve in front of the lantern. Connect two chains to the post that connect to the wall at the top and midpoint of the stairwell when people are present in the lantern room.
- Raise the existing rail in front of the lantern to 40 inches to meet OSHA standards (the present rail is 33 inches).
- Add a midcourse rail in front of the lantern.
Presently, if a child was in the lantern room, they could slip through and fall to the stairwell below.
- Post a sign at the entrance to the tower at the museum level: "Caution: Steep and Narrow Stairway. Use Handrail."

Exterior Modifications

- Raise the exterior decking rail to 42 inches to meet OSHA standards (the present rail is 31 inches). This modification is subject to a not-to-exceed cost of \$10,000.
- Lighthouse masonry deck repairs with 4Culture Grant.

Procedures

- No more than four individuals plus the tour guide in the tower at any one time including those in the stairwell or on the outer deck. A volunteer will be posted at the museum level during events to ensure no additional entrance.