



MASONRY / STONE REBUILD:

- REFER TO STRUCTURAL DRAWINGS AND PROVIDE SHORING DRAWINGS AS REQUESTED.
- EXISTING MARBLE SHALL BE SALVAGED. CONTRACTOR TO PROVIDE SHOP DRAWINGS AND A MATRIX THAT CATALOGUES EACH STONE THAT IS REMOVED, INCLUDING COPING STONES. EACH STONE SHALL BE TAGGED AND CORRESPOND TO THE MATRIX TO FACILITATE RE-INSTALLATION OF STONE WITH THE RE-BUILD.

ALLOCATIONS:

- QUANTITIES THAT HAVE BEEN ALLOCATED ARE TO BE DETERMINED IN FIELD. UPON FULL SCAFFOLDING, INSPECTION IS TO BE PERFORMED TO DETERMINE AND QUANTIFY ANY ADDITIONAL WORK. COORDINATION AND CONFIRMATION BETWEEN ARCHITECT, CONTRACTOR AND OWNER'S REP IS REQUIRED.

DOB STAMPS & SIGNATURES

DOB BSCAN