



CONTRACTOR TO PROTECT EXISTING PAINTED WOOD CEILING, WHICH IS TO REMAIN, THROUGHOUT CONSTRUCTION SCOPE. IF ANY FINISHED WOOD IS REQUIRED TO BE REMOVED AS A RESULT OF INTERIOR SHORING OR STUCCO FINISHING THE CONTRACTOR SHALL CAREFULLY REMOVE, SAVE FOR RE-SETTING AND INSTALL AT APPROPRIATE STAGE OF WORK SCOPE COMPLETION. ANY EXISTING DETERIORATED WOOD SHALL BE BROUGHT UP TO THE ATTENTION OF THE ARCHITECT.

1A
A-502.00

CONTRACTOR TO REPLICATE MOULDING AROUND EXISTING STAINED GLASS WINDOWS AS PART OF REPAIR SCOPE. CREATE A DRAW MOLD OUT OF THE EXISTING AND RECREATE/BUILD USING PLASTER SYSTEM SPECIFIED FOR WALLS.

STAINED GLASS PROTECTION AND REPAIR SCOPE TO BE PROVIDED BY CONSULTANT FEMENELLA & ASSOCIATES. CONTRACTOR TO PROVIDE REQUIRED SCAFFOLDING AND ACCESS TO AREA FOR THE DURATION OF THEIR WORK.

CONTRACTOR TO REMOVE EXISTING LIGHTING AND ARTIFACTS AS REQUIRED FOR THE DURATION OF THE WORK SCOPE. SAVE FOR RE-SETTING AND COORDINATE WITH THE CHURCH OR IT'S CONSULTANT FOR STORAGE. INSTALL AT APPROPRIATE STAGE OF WORK SCOPE COMPLETION. (TYP)

1B
A-502.00

CONTRACTOR TO REPLICATE PERIMETER MOULDING AROUND EXISTING SPACE AS PART OF REPAIR SCOPE. CREATE A DRAW MOLD OUT OF THE EXISTING AND RECREATE/BUILD USING PLASTER SYSTEM SPECIFIED FOR WALLS.

1C
A-502.00

CONTRACTOR TO REPLICATE PERIMETER MOULDING AROUND EXISTING SPACE AS PART OF REPAIR SCOPE. CREATE A DRAW MOLD OUT OF THE EXISTING AND RECREATE/BUILD USING PLASTER SYSTEM SPECIFIED FOR WALLS.

2
A-502.00

NEW PLASTER SCOPE. REMOVAL SHALL BE PART OF ABATEMENT SCOPE.

PEWS AND WAINSCOTING:

ANY PORTIONS OF THE PEWS AND WAINSCOTING ABUTTING MASONRY REPLACEMENT SHALL BE TEMPORARILY REMOVED BY THE CONTRACTOR IN A CAREFUL AND SYSTEMATIC MANNER. SAVE FOR RE-SETTING AND COORDINATE WITH THE CHURCH OR IT'S CONSULTANT FOR STORAGE. INSTALL AT APPROPRIATE STAGE OF WORK SCOPE COMPLETION. (TYP)

INTERIOR PROTECTION:

CONTRACTOR TO PROVIDE ALL NECESSARY INTERIOR PROTECTION REQUIRED TO INSTALL THE SCOPE OF WORK AND MINIMIZE INTERRUPTION TO THE CHURCH AND THE SERVICES IT PROVIDES. IF THE AREA IS SECTIONED OFF WITH TEMPORARY BARRIERS, CONTRACTOR SHALL COORDINATE EXTENT AND SCOPE WITH THE CHURCH. NO BARRIER OR PROTECTION TO IMPEDE ANY EMERGENCY EXITS OR PATHS OF TRAVEL WITHIN THE CHURCH.

SHORING:

REFER TO STRUCTURAL DRAWINGS FOR REQUIRED SHORING DRAWINGS. PROVIDE ALL REQUIRED INTERIOR PROTECTION TO PROTECT FINISHES AND ITEMS TO REMAIN FOR THE DURATION OF ITS PLACEMENT. REMOVAL AND RESETING OF ANY EXISTING ITEMS ARE WITHIN THE CONTRACTORS SCOPE.

SCAFFOLDING:

INTERIOR PIPE SCAFFOLDING REQUIRED TO PERFORM THE SCOPE OF WORK AND STAINED GLASS WINDOW RESTORATION IS TO BE PROVIDED BY THE CONTRACTOR. SCAFFOLDING SHALL MEET ALL REQUIREMENTS ESTABLISHED BY THE NEW YORK CITY BUILDING CODE.